LOCK # 21
FLOODED July 1 1958

The Robert H. Saunders - St. Lawrence Generating Station
Dam 167 ft heigh with an overall length of 3,300 feet

CORNWALL CANAL SYSTEM DEVELOPMENT
1779 - 1783 : First Canal system
1804 - 1817 : Changes to First system
1843 - 1848 : 2ND Canal system (200 ft long, 45 ft wide, 9 ft deep) 1st enlargement
1876 - 1904 : 3RD Canal system (270 ft long, 45 ft wide, 14 ft deep) 2nd enlargement
1905 : Winches installed

Lock 21 Lock constructed 1 April 2 Sep. 1885
weir constructed 3 April - 1 June 1886

The Cornwall Canal was operated and administered unil 1958 by the Department of Railways & Canals
(no change in elevation)
Guard Lock - Is 270 feet in length between the gate quoins, 45 feet in width between the side walls and 14 feet clearence over the sill
Lock 21 was Located at the upper entrance of the (11 miles long) Cornwall Canal which was built to circumvent the great rapids of the Long Sault

Lock 21 was constructed was enlarged rebuilt in 1885/86
to accomodate the "14-footer"
The canal was adapted so as to permit the passage of boats (1876-1904)
requiring a draught of 14 feet (4.2 m)

Acknowledge : Public Archives Canada

Deposit $19,500 5% of Contract
$390,000 Total cost