HOLLOW QUOINS—To be alternately headers and stretchers, the former at least 5 feet face and 6 feet depth of bed; the latter 6 feet face and 5 feet bed in the top courses, increasing in dimensions downward at a rate suited to the batter of the wall. The headers are to be checked so as to bond at least one foot over the face stones of the recess. The nose of the quoins to be rounded, the radius gradually increasing downwards at a rate corresponding to the batter of the wall; the hollow to be dressed out true and smooth to a radius of 8 inches, from which the heel is to run obliquely to the line of the recess wall. Patterns for the hollow quoins will be furnished by the Engineer, after the Contractor has given the height of the courses he intends to use.

RECESS QUOINS—To be also 5 by 6 feet, laid alternately out-bond and in-bond, bevelled, as shown on plan; the header to be checked so as to make return-bond with the ashlar of the recess.

CHAIN WELLS AND MAN-HOLES.—There are to be eight chain-wells in the position indicated on the plan; each well will be two feet square inside, and the man holes from them to the front of the lock walls are to be made at the angles and widths to permit the play of the chains, and of such height as the Engineer may direct.

The sills and lintels to be of stone, sufficiently large to reach across the opening and one foot on each side; the bottom to slope towards the inside of the lock, so as to prevent the chain, when slack, lodging in the man-holes; sheaves for the drag chains are to be inserted and secured near the upper inner angles of the man-holes. The face stones of the wells and man-holes to be of like dimensions, and cut in like manner as the face stones of the recess walls, and are to be properly bonded over and with each other at the angles.

CHECKS—For the reception of stop-water timbers, two checks are to be formed in the face of each of the wings at both ends of the lock; they are to be arranged as shown on the plan, be 3 feet apart, 12 inches wide, and 4 inches deep at the top, and made plumb in the rear.

COURSED WORK.—For the face of the chamber walls and for that part of the north side of the north wall three feet above the foundation may be 9 inches high and upwards; but a course once commenced must be continued the same height throughout, and in no case will more than two courses be allowed to make up the height of one course of cut stone. They must be at least 20 and 30 inches depth of bed in alternate courses, and have not less than 2 feet length of face in line of wall. In every course there are to be headers of at least 20 inches length of face and 4 feet depth of bed, placed not more than 12 feet from centre to centre.

In all cases the rear part of both headers and stretchers must be at least two-thirds the length of their face.

The face of the stones must be dressed to the batter of the wall, boucharded, and the arrises kept good. The upper and lower beds must be made parallel for their entire depth, and the end joints kept full for at least 9 inches back from the face. The whole to be dressed so that the horizontal and vertical joints of the stone, when in place, shall not exceed three-eighths of an inch. In the three lowest courses on the north side of the north wall the stones in each course must alternately be $2\frac{1}{2}$ and $3\frac{1}{2}$ feet depth of bed, dressed as above described and laid with offsets of 6 inches as previously stated.

BACKING.—To be of an approved class of large well-shaped stones, not less than 6 inches in thickness and 4 feet area of bed, laid level in full mortar beds, and properly bonded throughout the wall; where the depth of the face stone equals or exceeds 12 inches, two thicknesses of backing may be used, provided their joint depth does not exceed that of the face-work.

The lower beds, if necessary, must be picked off so as to insure a uniform and equal bearing on the course below. No pinning will be permitted.